

**ENGINEERING THAT WORKS FOR YOU**

**Development & Infrastructure- Tank Farm Installation and Bund Wall**

Contract	Value	Location
3 Weeks	£80k	Billingham

**Client**

**Growhow UK**

Haverton Hill Rd  
Billingham  
TS23 1PJ



**Project Description:**

This project was for various works within the Nitrogen Production Centre at the Billingham site and included the construction of a tank farm area with reinforced concrete walls and floor slabs to create a bunded area around the nitric acid plant. The cast in-situ walls were cast with Toproc high performance sulphate resistant concrete.



Works included, general clearance of the site and taking up of existing precast concrete paving slabs, excavation of material and preparation of the excavated surface for erection of the tank farm installation. The 250m long bund surrounding the tank was 300mm x 1000mm and cast on existing foundations.

